

CORPORATION OF THE TOWNSHIP OF ESQUIMALT

BYLAW NO. 2937

A Bylaw to authorize a Housing Agreement
under section 483 of the *Local Government Act*

THE MUNICIPAL COUNCIL OF THE TOWNSHIP OF ESQUIMALT, in open meeting assembled, enacts as follows:

1. This bylaw may be cited as the "*HOUSING AGREEMENT (669 Constance Avenue) BYLAW, 2018, NO. 2937*".
2. The Mayor and the City's Corporate Officer are authorized to execute the Housing Agreement:
 - (a) set out in Schedule A,
 - (b) between the Township and STANDINGSTONE DEVELOPMENTS LTD., INC.NO. BC0776378, and
 - (c) that applies to the land known as 669 Constance Avenue, legally described as:

PID: 030-431-026, LOT 1, SUBURBAN LOTS 43 AND 44, ESQUIMALT DISTRICT, PLAN EPP76107.

READ a first time by the Municipal Council on the 25th day of June, 2018.

READ a second time by the Municipal Council on the 25th day of June, 2018.

READ a third time by the Municipal Council on the 25th day of June, 2018.

ADOPTED by the Municipal Council on the ---- day of -----, 2018.

BARBARA DESJARDINS
MAYOR

ANJA NURVO
CORPORATE OFFICER

HOUSING AGREEMENT

(Pursuant to Section 483 of the *Local Government Act*)

THIS AGREEMENT is made the 18 day of June, 2018.

BETWEEN

THE CORPORATION OF THE TOWNSHIP OF ESQUIMALT

1229 Esquimalt Road
Esquimalt, BC V9A 3P1

(the "TOWNSHIP")

AND

STANDINGSTONE DEVELOPMENTS LTD. INC. NO. BC0776378

1920 – 10020 101A Avenue
Edmonton, Alberta T5J 3G2

(the "OWNER")

RECITALS:

- A. Under section 483 of the *Local Government Act*, R.S.B.C. 2015 c.1 ("*LGA*") the Township may, by bylaw, enter into a Housing Agreement with an owner regarding the occupancy of the housing units identified in the Agreement, including but not limited to terms and conditions referred to in section 483(2) of the *Local Government Act*;
- B. The Owner is the registered owner in fee-simple of those lands with a current civic address of 669 Constance Avenue in the Township of Esquimalt in the Province of British Columbia, and legally described as:

PID: 030-431-026

LOT 1 SUBURBAN LOTS 43 AND 44 ESQUIMALT DISTRICT PLAN
EPP76107

(the "Lands");

- C. The Owner has submitted an application to the Township to rezone the Lands from RM-4 [Multiple Family Residential] and RM-1 [Low Density Townhouse Multiple Family Residential] to CD No.107 [Comprehensive Development District No. 107] further to ZONING BYLAW, 1992, NO. 2050, AMENDMENT BYLAW NO. 2915 ("**Rezoning Bylaw**"), and acknowledges that it is in the public interest that the use and occupation of the Lands be limited, in particular given the Owner's intent to construct a 12 storey, mass timber, 83 unit, multiple family, prefabricated, residential building ("**Corvette Landing**") which building is intended to include a glass enclosed 18 foot lobby, multiple purpose room and amenity space located at grade off Admirals Road and situated above mechanical and storage areas, 3 levels of underground parking consisting of 83 spaces, and Dwelling Units which will be available for rental or owner-occupied purposes (collectively, the "**Proposed Development**");
- D. The Owner and the Township wish to enter into this Agreement, as a Housing Agreement pursuant to section 483 of the *Local Government Act*, to secure the agreement of the Owner with respect to the matters noted herein (the "**Agreement**" or "**Housing Agreement**"), the parties acknowledging that Notice of this Housing Agreement will be placed on title to the Lands and will be binding on future owners in accordance with LGA s.483(6).

NOW THIS AGREEMENT WITNESSES that pursuant to section 483 of the *Local Government Act*, and in consideration of the premises and covenants contained in this Agreement, the parties agree each with the other as follows:

1. DEFINITIONS

- 1.1. Unless otherwise stated, the definitions of the Township's ZONING BYLAW, 1992, NO. 2050 ("**Zoning Bylaw**"), apply to this Agreement.
- 1.2. The following words and terms have the following meanings:
- (a) "**Designated Units**" means the 10 Dwelling Units identified in **Schedule A**;
 - (b) "**Dwelling Units**" means the units dedicated to or used for residential uses; and

- (c) **“Individual with Special Needs”** means an individual who requires additional or specialized services or accommodations by reason of one or more difficulties such as physical, emotional, behavioral, developmental, or otherwise, as evidenced in writing by the appropriate Federal or Provincial ministry or agency.

2. DESIGNATED HOUSING

- 2.1. The Owner will construct the Designated Units identified in **Schedule A** such that they will accommodate, or are capable of being adapted to accommodate, an Individual with Special Needs in accordance with the minimum requirements set out in **Schedule B**, all to the satisfaction of the Director of Development Services and with such amendments as may be agreed upon by the Director of Planning and Development.
- 2.2. The Designated Units are intended for occupancy by Individuals with Special Needs, however the Township acknowledges that there may be times when such occupancy is not possible following the good faith efforts of the Owner to secure such occupancy in accordance with this Agreement.
- 2.3. The Owner will not sell, transfer or otherwise dispose of the Designated Units except in accordance with the following requirements:
- (a) the Owner will exclusively market the Designated Units for sale to Individuals with Special Needs for fair market value for a period of 90 calendar days (the **“Initial Listing Period”**);
 - (b) the Owner will, prior to or concurrently with the commencement of the Initial Listing Period:
 - (i) advertise the Designated Units as being available on a priority basis to Individuals with Special Needs in a local paper for a period of not less than two weeks; and
 - (ii) hold at least one open house at the Owner’s sales centre which will be open only to people currently residing within the Township and Individuals with Special Needs no matter where they are currently residing;

and the Owner agrees to provide the Director of Development Services with drafts of the advertising and information about the open house prior to publishing the advertising and prior to holding the open house such that the Director of Development Services has sufficient time to review same and provide recommendations for suggested content and the Owner further agrees to include the

contact information of a Township representative in such advertising and at the open house if requested to do so by the Director of Development Services;

- (c) the Owner will consider offers received from Individuals with Special Needs during the Initial Listing Period in accordance with the following:
 - (i) the Owner will act in a commercially reasonable manner having regard to the offer price, the buyer's subject conditions, and the proposed closing date in deciding whether to accept or reject such offer;
 - (ii) the Owner will not discriminate on the basis of physical, emotional, behavioral, or developmental needs;
 - (iii) in the event the Owner does not accept an offer received from an Individual with Special Needs during the Initial Listing Period and the offer price is not less than 5% below the listing price, then the Owner will provide the Township with a copy of the offer together with the Owner's written reasons for not accepting the offer, PROVIDED THAT the consent of the offeror to disclose such information to the Township is first obtained by the Owner using commercially reasonable efforts, failing which the Owner will provide the essential non-personal details of the offer, including but not limited to offer price, closing date, conditions and any other information relevant to the Owner's decision; and
 - (iv) in the event any or all of the Designated Units are not sold to Individuals with Special Needs during the Initial Listing Period, the Owner may then offer any or all of the Designated Units for sale to members of the public;
 - (v) if the Owner reduces the listing price or proposes to transfer a unit to a member of the public for less than or equal to the an offer received from an Individual with Special Needs, the Owner must first offer such price and terms to Individuals with Special Needs, in particular those that identified themselves to the Owner during the Initial Listing Period, and provide evidence of such to the Township;

and for greater clarity, the requirements set out in this section 2.4 will apply to every successor in title to the Designated Units except for section 2.4(b)(i) and (ii).

3. ACCESSIBILITY

- 3.1. All common areas located within the Proposed Development, and a minimum of four (4) dwelling units, will be designed and constructed for wheelchair accessibility.
- 3.2. Driveways leading to the four accessible parking spaces set out in **Schedule C** must be designed for wheelchair accessibility.

4. NO RESTRICTION ON RENTAL UNITS

- 4.1. The Owner covenants and agrees that the Proposed Development will not restrict rental of the Dwelling Units by non-owners, other than restricting tourist accommodation/short-term rentals of less than 30 days, and if stratified, the Dwelling Units may be occupied by the owners of the individual Dwelling Units in addition to being available as rental units to non-owners.
- 4.2. The Owner covenants and agrees that it will not apply to deposit a strata plan for the Proposed Development to be constructed on the Lands unless the strata bylaws in no way restrict rental of the Dwelling Units, other than restricting tourist accommodation/short-term rentals of less than 30 days.

5. ADMINISTRATION & MANAGEMENT - REPORTING

- 5.1. Within thirty (30) days of receipt of request from the Township, the Owner must provide a report in writing that identifies the following for the Proposed Development, or portions thereof, respectively:
 - (a) the number, type, and location by suite number, of Designated Units developed and maintained including identification of any modified Dwelling Units that would alter their classification as a Designated Unit;
 - (b) the number, type (e.g. 1-bedroom, 2-bedroom), and location by suite number, of Dwelling Units that are being rented to individuals (i.e. not owner-occupied) or are available for rent to individuals;
 - (c) any changes or proposed changes to strata bylaws that may affect the terms of this Agreement;

- (d) subject to applicable privacy legislation (however noting the authority under section 59(1) of the *Community Charter*), the name and contact information of all individuals, governmental agencies or corporations that use, occupy, manage or operate more than one Designated Unit, along with the applicable suite numbers; and
- (e) such further information identified in the request from the Township, provided such is relevant to the interpretation, administration or enforcement of this Housing Agreement.

5.2. The parties acknowledge and agree that:

- (a) the reporting requirements set out in this Article 5 will not be imposed more than once per year, unless there are reasonable grounds to believe that there may be a breach, in fact or in spirit, of this Housing Agreement (as determined in the Township's sole discretion, for the purposes of reporting);
- (b) there are no reporting requirements unless the Township so requests; and
- (c) the Owner will be responsible for the reporting requirements set out in this Article 5 until such time as the Strata Corporation formed in respect of the Proposed Development holds its first annual general meeting, and thereafter, the Strata Corporation will be responsible for the reporting requirements set out in this Article 5.

6. NOTICE IN LAND TITLE OFFICE

- 6.1. Notice of this Agreement will be filed in the Land Title Office by the Township at the cost of the Owner in accordance with section 483 of the *Local Government Act*, and this Agreement is binding on the parties to this Agreement as well as all persons who acquire an interest in the Lands after filing of the Notice.

7. RELEASE AND INDEMNITY

- 7.1. The Owner covenants and agrees to indemnify and save harmless the Township from any and all claims, causes of action, suits, demands, fines, penalties, costs or expenses or legal fees (on a solicitor-client basis) (collectively, "**Claims**") whatsoever, in law or equity, which anyone has or may have against the Township or which the Township incurs as a result of any loss, damage, deprivation, enrichment or injury, including economic loss, arising out of or connected with the restrictions or requirements of this

Agreement, the breach of any covenant in this Agreement, or the use, occupancy and tenure of the Lands contemplated under this Agreement EXCEPT TO THE EXTENT such Claims result from the gross negligence of the Township.

- 7.2. The Owner and Strata Corporation release and forever discharge the Township of and from any Claims whatsoever, in law or equity, which the Owner or Strata Corporation can or may have against the Township for any loss, damage, deprivation, enrichment or injury, including economic loss, arising out of or connected with the restrictions or requirements of this Agreement, the breach of any covenant in this Agreement, or the use, occupancy and tenure of the Lands contemplated under this Agreement.

8. GENERAL PROVISIONS

- 8.1. **NOTICE:** Any notice permitted or required by this Agreement to be given to either party must be given to that party at the address set out above, or to any other address of which the party has given the other party notice in writing expressly for the purposes of this Agreement.
- 8.2. **CONFLICT:** In the event of a conflict between the terms of this Agreement and the provisions of Township Bylaws in relation to use or density, the bylaws will prevail in accordance with section 483(3) of the *Local Government Act*.
- 8.3. **BINDING EFFECT:** This Agreement will enure to the benefit of and be binding upon the parties hereto and their respective heirs, administrators, executors, successors, and permitted assignees, and in accordance with section 483(6) of the *Local Government Act*.
- 8.4. **TIME:** Time is to be the essence of this Agreement.
- 8.5. **WAIVER:**
- (a) No provision of this Agreement is to be considered to have been waived by a party unless the waiver is expressed in writing by the party.
 - (b) The waiver by a party of any failure on the part of the other party to perform in accordance with any of the terms or conditions of this Agreement is not to be construed as a waiver of any future or continuing failure, whether similar or dissimilar.
- 8.6. **MODIFICATIONS:** The Owner acknowledges that it is within the Township's sole discretion to consent or not to consent to modifications of this Agreement and that such consent may be withheld for any reason.

8.7. **CUMULATIVE REMEDIES:** No remedy under this Agreement is to be deemed exclusive but will, where possible, be cumulative with all other remedies at law or in equity.

8.8. **RELATIONSHIP OF PARTIES:**

(a) No provision of this Agreement may be construed to create a partnership or joint venture relationship, an employer-employee relationship, a landlord-tenant, or a principal-agent relationship.

(b) The Owner is solely responsible for all costs and expenditures required to fulfill its obligations under this Agreement, whether those costs and expenses are specifically referred to in this Agreement.

8.9. **FURTHER ASSURANCES:** The Owner will do, execute, and deliver, or cause to be done, executed, and delivered all such further acts, documents and things as may be reasonably required from time to time to give effect to this Agreement.

8.10. **ENTIRE AGREEMENT:**

(a) This Agreement contains the entire agreement and understanding of the parties with respect to the matters contemplated by this Agreement and supersedes all prior and contemporaneous agreements between them with respect to such matters.

(b) No representations, warranties or conditions, express or implied, oral or otherwise, have been made other than those expressed in this Agreement.

8.11. **NO RESTRICTION ON TOWNSHIP AUTHORITY:** Except as required by section 483 of the *Local Government Act*, nothing contained or implied in this Agreement:

(a) prejudices or affects the rights, powers or discretion of the Township in the exercise of its functions under any public or private statutes, bylaws, orders and regulations, all of which may be fully and effectively exercised in relation to the Lands as if the Agreement had not been executed and delivered by the Owner;

(b) imposes any legal duty or obligation, including any duty of care or contractual or other legal duty or obligation, to enforce this Agreement or the breach of any provision in this Agreement; or

- (c) imposes any public law duty, whether arising from the principles of procedural fairness or the rules of natural justice, on the Township with respect to its exercise of any right or remedy expressly provided in this Agreement or at law or in equity.

- 8.12. **SEVERABILITY:** Each article of this Agreement is severable. If any provision of this Agreement is held to be illegal or invalid by a Court of competent jurisdiction, the provision may be severed and the illegality or invalidity must not affect the validity of the remainder of this Agreement.
- 8.13. **ACKNOWLEDGEMENT:** The Owner acknowledges having been directed to obtain independent legal advice and having read and fully understood all the terms and conditions of this Agreement. The Owner confirms that this Agreement has been entered into voluntarily.
- 8.14. **COUNTERPARTS:** This Agreement may be executed in counterpart with the same effect as if both parties had signed the same document. Each counterpart is deemed to be an original. All counterparts are construed together and constitute one and the same Agreement.
- 8.15. **APPLICABLE LAW:** This Agreement is to be construed in accordance with and governed by the laws applicable in the Province of British Columbia.

IN WITNESS WHEREOF the parties have set their hands and seals as of the day and year first above written.

TOWNSHIP OF ESQUIMALT

by its authorized signatories

Mayor

Chief Administrative Officer

)
)
)
)
)
)
)
)

STANDINGSTONE DEVELOPMENTS LTD.

INC. NO. BC0776378,

by its authorized signatories

Name:

Name:

PRIORITY: VANCOUVER CITY SAVINGS CREDIT UNION, INC NO. FI 97, (the "Chargeholder,") is the registered holder of a charge by way of MORTGAGE and ASSIGNMENT OF RENTS against the Lands, registered under No. CA5999996, and CA5999997, respectively (the "Charges"), agrees with the Township, in consideration of the sum of Ten Dollars (\$10.00) paid by the Township to the Chargeholder (receipt and sufficiency acknowledged), that the Agreement will be an encumbrance upon the Lands in priority to the Charges in the same manner and to the same effect as if the Agreement had been dated and registered prior to the Charges.

VANCOUVER CITY SAVINGS CREDIT UNION, INC NO. FI 97

by its authorized signatories

Name:

Name:

Karen O'Mara
Loan Security Coordinator
Community Business Administration

Katie McGowan
Coordinator
Community Capital

1001338-3

SCHEDULE "A"
DESIGNATED UNITS

The Designated Units include the following Dwelling Units as further identified in bold on the architectural plans attached:

- Unit 101 - 1 Bedroom
- Unit 203 - 1 Bedroom - Wheelchair accessible
- Unit 207 - 2 Bedroom - Wheelchair accessible
- Unit 208 - 2 Bedroom - Wheelchair accessible
- Unit 209 - 2 Bedroom - Wheelchair accessible
- Unit 302 - 1 Bedroom
- Unit 305 - 1 Bedroom
- Unit 307 - 1 Bedroom with a tech space
- Unit 406 - 1 Bedroom
- Unit 408 - 1 Bedroom with a tech space

In the event of a conflict between the final unit numbers issued by the Township and the units identified in the architectural plans attached, the units identified in the architectural plans attached will prevail.

This architectural floor plan depicts a building with a complex layout. The building is oriented vertically, with a long, narrow central section and a large, irregularly shaped outdoor area to the left. The outdoor area is enclosed by a dashed line, suggesting a boundary or fence. The building's footprint is defined by solid lines, with various rooms and corridors. The rooms are labeled with numbers and names: 101 (101), 102 (102), 103 (103), 104 (104), and 105 (105). The room labeled 101 is a large, rectangular space with a cross-hatched pattern. The room labeled 102 is a smaller, rectangular space. The room labeled 103 is a rectangular space. The room labeled 104 is a rectangular space. The room labeled 105 is a rectangular space. The plan also shows a large, irregularly shaped outdoor area to the left of the building, enclosed by a dashed line. The overall layout suggests a multi-story building with a mix of indoor and outdoor spaces.

[illegible]

**Standing Stone
Developments Ltd.**
1000 West 10th Ave.
Suite 1000
Calgary, Alberta T2C 1A5
Phone: 403.243.2222
Fax: 403.243.2223

ARCHITECT
LWPAC
Landscape Architecture
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Structural
Structural Engineering Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Building Envelope /PH
Building Envelope Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Building Code
Building Code Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Civil Engineer
Civil Engineer Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Landscape Architect
Landscape Architect Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222


Geotechnical Engineer
Geotechnical Engineer Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Electrical
Electrical Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Mechanical
Mechanical Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

Corvette Landing
Corvette Landing Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222

AAP.06
AAP.06 Inc.
1111 17th Ave. SW
Suite 100
Calgary, Alberta T2C 1A5
Phone: 403.243.2222



Level 2
1:100

**Standing Stone
Developments Ltd.**

Company Office, Tony Grant
1820 101st Ave SW
Edmonton, AL, T6C 2A2
Email: tony@standing-stone.com
standing-stone.com
Phone: (780) 243-8337 (Home)

Architect

LWPAC

Long without Practice in Architecture Culture

Other Long, Architect ADHC

333 West 305 Avenue
Vancouver, B.C. and 10th, Canada
Phone: 604.681.1111
Phone: 604.717.1111

Structural
Equilibrium Consulting Inc.
Robert MacKay
227-281 West 8th Avenue
Vancouver, B.C. V5Z 1A2
E-mail: rmackay@equimac.com
Phone: +1 604 756-1421

Building Envelope/PH
K&N Building Science Inc.
Graeme French
114 W 8th Avenue

Phone: 404 473 1181 x 250

Building Code
GAS, COMBUSTIBLE LTD.
3401 Peachtree
409 Spruillville Street, Suite 300
Vancouver, BC V6C 1J7
Email: info@bcl.ca
Phone: 604 681 5441 Ext. 112

Civil Engineer
McElreath Consulting Services Ltd.
Arthur Darroch
Suite 100, 3940 Quebec Street

Phone: 778 746 7417

Landscape Architect

Landscape North Group (B.C.) Inc.
James Parlane
3141 Glenhurst Street
Vancouver, B.C. V6H 1S1
Email: jparlane@landscape.ca
Phone: 250 366 3334

Geotechnical Engineer

GeoPacific Consultants
kshah@geopacific.ca

Traffic
 Ward & Associates
 Union Station
 Suite 421, 345 East Street
 Victoria, BC V8W 1G2
 (Toll-free) 1-800-363-6333
 Phone 250-363-6333

Electrical
 415
 Joe Smith

Mechanical

And More

Ken Shaw
15504-B West Hastings Street
Vancouver, B.C., Can. V6A
E-mail: shawken@shaw.ca
Phone: 604-436-1575

Not for Certification
All Dispositions to be verified online

June 15, 2019	

Copyright reserved. This design and the drawings are the exclusive property of L'Oréal when Parfums in Architecture Culture Inc. and cannot be used for any other purpose without the written consent of the architect. This drawing is to be used for construction, distribution, advertisement and used for these purposes by the architect. Prior to commencement of the work the architect shall verify all measurements, dimensions, amounts and loads to identify any errors and omissions, ascertain any discrepancies between the drawings and the field conditions and report the same to the architect. The architect shall be responsible for any errors, omissions, and omissions, and shall be responsible for the accuracy of the drawings.


Product

CORVETTE LANDING

197 Condado Avenue, Condado Terrace,
MA 01915, 821-444-1111
FAX: 821-444-1111
E-mail: info@corvette.com
Landing, Inc. is a subsidiary of
L & L, Inc. 1-800-545-5455

Plan 0017063	AAP.07	Title: L3 Area Plan
--------------	--------	---------------------

Make # 100	Price: 13.00
Date: 11-06-05	Serial:
Printer: author	Barcode:
Reviewed: OK	



Level 4
1 : 100

SCHEDULE B

Page 1 of 7

BASIC ADAPTABLE HOUSING

BASIC ADAPTABLE HOUSING

The following Basic Adaptable Housing features are required in all newly-constructed buildings serviced by an elevator containing apartment or congregate housing uses.

The requirements of Schedule "F" Section (g) do not apply to non-congregate housing apartment units smaller than 42 m (450 ft) provided that a bathroom consistent with Section (g)(iii) of this Schedule "F" is available to all occupants within the building.

(A) Building Access

- i. Barrier-free access from the street shall be provided to each dwelling unit and to each type of common amenity space.
- ii. Barrier-free access from a private parking area shall be provided to each dwelling unit and to each type of common amenity space.
- iii. Access to the elevator shall be provided from both the street entry and a private parking area entry.
- iv. A covering over a level building entry area, of 1500mm by 1500mm shall be provided.
- v. No intercom user functions shall be higher than 1220mm above the finished paved area.
- vi. Wiring for an automatic door opener shall be provided at each of the required barrier- free entries.

(B) Doors and Doorways

- i. The minimum clear opening for all suite entry doors and doors in common areas shall be no less than 850 mm. (See Figure 1)
- ii. The minimum clear opening for all interior doors within a dwelling unit shall be no less than 800mm. (See Figure 1)
- iii. Doors in all suites and common areas shall be operable by devices that do not require tight grasping or twisting of the wrist.




FIGURE 1 – CLEAR OPENING MEASUREMENT FROM DOORS

BASIC ADAPTABLE HOUSING

(C) Manoeuvring Space at Doorways

- i. Suite entry doors and door assemblies in common areas (except those which are not self-closing) shall have a clear and level area which is not less than the following:
 1. Where the door swings toward the area (pull door), 1220mm long by the width of the door plus at least 300mm clear space on the latch side. (See Figure 2)




FIGURE 2 – FRONT APPROACH, PULL SIDE

2. Where the door swings away from the area (push door), 1220mm long by the width of the door plus at least 300mm clear space on the latch side. (See Figure 3)




FIGURE 3 – FRONT APPROACH, PUSH SIDE

BASIC ADAPTABLE HOUSING

3. Where there are doors in a series in common areas, there must be separation of at least 1220mm plus the width of the door. (See Figure 4)




FIGURE 4 – SEPARATION OF DOORS IN SERIES

(D) Corridor widths

Common corridors shall be no less than 1220mm wide.

(E) Thresholds

Thresholds shall be kept to a minimum, and in all suites and common areas shall not exceed 13mm.

(F) Outlets and Switches

- i. Light switches shall be located between 1015mm and 1120mm from the floor.
- ii. Electrical outlets, cable outlets, and telephone jacks shall be located not less than 450mm from the floor.

BASIC ADAPTABLE HOUSING

(G) Bathrooms

- i. There shall be at least one bathroom with toilet and sink on the main entry level of each suite which provides enough floor space to be the following space requirements:
 1. Clear floor area of 760mm by 1220mm beyond the swing of the door. (See Figure 5)




FIGURE 5 – CLEAR FLOOR AREA BEYOND SWING OF DOOR

2. Clear floor area at the tub of 760mm by 1220mm, or 1220mm by 760mm, measured from the foot end of the tub. (See Figure 6)




FIGURE 6 – CLEAR FLOOR AREA AT TUB

BASIC ADAPTABLE HOUSING

3. Clear floor area at the sink of 760mm by 1220mm positioned for a parallel approach and centred on the sink. (See Figure 7)




FIGURE 7 – CLEAR AREA AT SINK

4. Toilets shall meet the following space provisions: (See Figure 8)
 - a. Lateral distance from the centre line of the toilet to a bathtub or sink shall be 455mm minimum on one side and 380mm minimum on the other. Where the toilet is adjacent to a wall, the lateral distance from the centre line of the toilet to the wall shall be 455mm with 380mm minimum on the other side.
 - b. Clear floor area at the toilet of 1420mm minimum (measured from the wall behind the toilet) by 1220mm minimum (measured from a point 455mm from the centre line of the toilet on the side designated for future grab bars.)
 - c. The vanity or sink on the wall behind the toilet may overlap the clear floor required for the toilet.





FIGURE 8 – CLEAR FLOOR AREA AT TOILET

BASIC ADAPTABLE HOUSING



**FIGURE 9 – EXAMPLES OF BATHROOMS WITH FLOOR AREA TO SUITE
“MINIMALLY ACCESSABLE” REQUIREMENTS**

BASIC ADAPTABLE HOUSING

- ii. Solid blocking in walls around toilets, tub/shower, and behind towel bars shall be provided in all bathrooms as illustrated in Figure 10.
- iii. Where bathrooms are provided to serve common amenity spaces, at least one shall be wheelchair accessible as described in the B.C. Building Code (1998) Sentence 3.7.4.8.(1)





FIGURE 10 – BLOCKING REQUIREMENTS

SCHEDULE C

① P1 Floor Plan Sampled
1:100



Standing Stone
Developments Ltd.

Architect
LWPAC
1000 West 10th Avenue, Suite 100
Calgary, Alberta T2C 1A8
Phone: (403) 243-1111
Fax: (403) 243-1112
Email: info@lwpac.ca
Website: www.lwpac.ca

Structural
Building Envelope/PH
Building Code
Civil Engineer
Mechanical
Electrical
Geotechnical Engineer
Landscape Architect
Interior Designer
Architectural Photographer
Construction Manager
Construction Inspector
Construction Safety Officer
Construction Superintendent
Construction Worker
Construction Equipment Operator
Construction Material Supplier
Construction Subcontractor
Construction Consultant
Construction Insurance Broker
Construction Legal Counsel
Construction Financial Analyst
Construction Project Manager
Construction Quality Control
Construction Safety Manager
Construction Training Coordinator
Construction Environmental Coordinator
Construction Health and Safety Officer
Construction Human Resources Manager
Construction Information Systems Manager
Construction Logistics Coordinator
Construction Procurement Manager
Construction Risk Management
Construction Scheduling Coordinator
Construction Cost Estimator
Construction Quantity Surveyor
Construction Valuation Specialist
Construction Claims Specialist
Construction Dispute Resolution
Construction Arbitration
Construction Mediation
Construction Conciliation
Construction Negotiation
Construction Dispute Resolution
Construction Arbitration
Construction Mediation
Construction Conciliation
Construction Negotiation

CORVETTE LANDING

Project No. X1.06

P1 Floor Plan

Scale: 1:100

Drawn: [Name]

Checked: [Name]

Approved: [Name]

Date: [Date]

