

D00	SITE SURVEY
D01	EXISTING SITE PLAN W/ PROPOSED BUILDING
D02	AVERAGE GRADE CALCULATION
D03	OVERALL SITE PLAN
D04	LEVEL PARKADE FLOOR PLAN
D05	LEVEL 1 FLOOR PLAN
D06	LEVEL 2 FLOOR PLAN
D07	LEVEL 3 to 5 FLOOR PLAN
D08	LEVEL 6 FLOOR PLAN
D08b	ROOF PLAN
D09	BUILDING ELEVATIONS
D10	BUILDING ELEVATIONS
D11	SUITE PLANS
D12	SUITE PLANS
D13	AREA SUMMARIES
D14	RENDERINGS
D15	EAST WEST SECTIONS
D16	EAST WEST SECTIONS
D17	EAST WEST SECTIONS
D18	NORTH SOUTH SECTIONS
D19	NORTH SOUTH SECTIONS
L01	LANDSCAPE CONCEPT PLAN



BC LAND SURVEYORS SITE PLAN OF:

Civic: 874 Fleming Street

**Legal: Lot B, Section 10,
Esquimalt District, Plan 25267**

Parcel Identifier: 002-900-246 in the Township of Esquimalt

SCALE 1 : 3 0 0

0 2 5 10 15 20

All distances are shown in metres.

Plot on C size sheet.

LEGEND

Elevations are to geodetic datum.


+ - denotes - existing elevation

Tree diameters are in centimetres.

Contour interval = 1.0 metres

Contours have been derived by digital terrain
modelling and any critical elevations must
be verified by field survey.

Lot Area = 3909 m²



August 7, 2018

File : 12,826 - 23
POWELL & ASSOCIATES
B.C. Land Surveyors
250-2950 Douglas Street
Victoria, BC V8T 4N4
phone (250) 382-8855

Setbacks are derived from field survey.

Parcel dimensions shown hereon are
derived from Land Title Office records.

This document shows the relative location
of the surveyed features and shall not be
used to define property boundaries.

The following non-financial charges are shown on
the current title and may affect the property.

M76301 - Undersurface Rights
1062606 - Undersurface Rights
A64775 - Restrictive Covenant

PRELIMINARY - NOT FOR CONSTRUCTION



LOW HAMMOND ROWE ARCHITECTS



ESQUIMALT RENTAL HOUSING
874 FLEMING STREET, ESQUIMALT, BC

scale

SITE SURVEY
date 2020.02.11

D00



PRELIMINARY - NOT FOR CONSTRUCTION



LOW HAMMOND ROWE ARCHITECTS




ESQUIMALT RENTAL HOUSING
874 FLEMING STREET, ESQUIMALT, BC

EXISTING SITE PLAN W/ PROPOSED BUILDING

scale 1:200 date 2020.02.11

D01







GREATER VICTORIA
HOUSING SOCIETY
Since 1956

AVERAGE GRADE CALCULATION
scale 1 : 200 date 2020.02.11

D02



PRELIMINARY - NOT FOR CONSTRUCTION



LOW HAMMOND ROWE ARCHITECTS



ESQUIMALT RENTAL HOUSING
874 FLEMING STREET, ESQUIMALT, BC

LEVEL PARKADE FLOOR PLAN
scale 1:150 date 2020.02.11
Revised: 2020.01.27

D04

PRELIMINARY - NOT FOR CONSTRUCTION

NOTE: ROAD ELEVATIONS ARE PRELIMINARY AND MAY CHANGE PENDING FINAL FRONTAGE DESIGN.



LOW HAMMOND ROWE ARCHITECTS



ESQUIMALT RENTAL HOUSING

874 FLEMING STREET, ESQUIMALT, BC

LEVEL 1 FLOOR PLAN
scale 1:150 date 2020.02.11

D05





GREATER VICTORIA
HOUSING SOCIETY
Since 1956

LEVEL 2 FLOOR PLAN
scale 1 : 150 date 2020.02.11

D06



FEB 11 2020

CORP. OF TOWNSHIP
OF ESQUIMALT
DEVELOPMENT SERVICES





GREATER VICTORIA
HOUSING SOCIETY
Since 1958

LEVEL 3 to 5 FLOOR PLAN
scale 1 : 150 date 2020.02.11

D07



**CORP. OF TOWNSHIP
OF ESQUIMALT
DEVELOPMENT SERVICES**



PRELIMINARY - NOT FOR CONSTRUCTION






GREATER VICTORIA
HOUSING SOCIETY
Since 1956

scale 1 : 150

ROOF PLAN **D08b**
date 2020.02.11






SOUTH ELEVATION.



WEST ELEVATION.



PRELIMINARY - NOT FOR CONSTRUCTION




SUITE TYPE B3 49.8 m² (535.8 sf)

1:50

BCH DESIGN GUIDELINES - 1 BEDROOM

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	49 m ²	YES	49.8 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1205 mm
5.3.2.1	Living Room seating capacity	4 seats	YES	4 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	920 mm
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	1015 mm
5.3.3.1	Dining Room seating capacity	4 seats	YES	4 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	1.5 m ² in Parkade TBD
5.5.1.1	Provide 2.3 sm of storage	YES	NO	BR
5.5.1	Provide Linen Closet	YES	YES	2525 mm
6.1.3	Counter Frontage Recornd.	2440 mm	YES	915 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	800 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	YES
6.2.3.1	3 Piece Bathroom	1	YES	815 x 1525 mm tub
	Shower (914 x 1220mm)	NO	NO	1
	Water Closet	YES	YES	1
	Lav Basin with Vanity	YES	YES	1

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.4.2	Bedroom type 1 B	YES	YES	9.30 m ²
	Type B: Min Area	9.30 m ²	YES	3050 mm
	Type B: Closet width	1500 mm	YES	2100 mm




SUITE TYPE C 73 m² (786 sf) & 77.8 m² (837.6 sf)

1:50


BCH DESIGN GUIDELINES - 2 BEDROOM

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	67 m ²	YES	72 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1570 mm
5.3.2.1	Living Room seating capacity	5 seats	YES	5 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	920 mm
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	1015 mm
5.3.3.1	Dining Room seating capacity	4 seats	YES	4 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	1.5 m ² in Parkade TBD
5.4.2	Bedroom type 1 A / 1 B	YES	YES	N/A
	Type A: Min Area	11.15 m ²	YES	11.17m ²
	Type A: Min Dimension	2800 mm	YES	2840 mm
	Type A: Closet width	1500 mm	YES	1805 mm
	Type B: Min Area	9.30 m ²	YES	9.45 m ²
	Type B: Min Dimension	2800 mm	YES	3000 mm
	Type B: Closet width	1500 mm	YES	1800 mm
5.5.1.1	Provide 2.3 sm of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	3020 mm
6.1.3	Counter Frontage Recornd.	2440 mm	YES	915 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	800 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	YES
6.2.3.1	3 Piece Bathroom	1	YES	815 x 1525 mm tub
	Shower (914 x 1220mm) or ST tub	YES	YES	1
	Water Closet	YES	YES	1
	Lav Basin with Vanity	YES	YES	1



SUITE TYPE B2 49.7 m² (535.4 sf) & 53 m² (570.6 sf)

1:50



SUITE TYPE A3 (ACCESSIBLE) 36 m² (387.9 sf)

1:50

BCH DESIGN GUIDELINES - STUDIO ACCESSIBLE

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	37 m ²	YES	36 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1170 mm
5.3.2.1	Living Room seating capacity	2 seats	YES	2 seats
5.3.2.2	Circulation spaces Min. Width	915 mm	YES	915 mm
5.3.2.3	Interior Corridor Recornd. Width	1067 mm	YES	1067 mm
5.3.3.1	Dining Room seating capacity	2 seats	YES	2 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	N/A
5.4.2	Bedroom type	N/A	N/A	N/A
5.5.1.1	Provide 2.3 sm of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	Entrance next to Fridge
6.1.3	Counter Frontage Recornd.	1860 mm	YES	2540 mm
6.2.2.2	Lav. Countertop Min. Width	800 mm	YES	915 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	800 mm
6.2.3.1	3 Piece Bathroom	1	YES	815 x 1525 mm tub
	Shower (914 x 1220mm)	YES	1	1
	Water Closet	YES	1	1
	Lav Basin with Vanity	YES	1	1
6.2.2.1	1500 mm turning radius	YES	YES	Both sides of Entry Door
	Inside Bedroom	YES	YES	Inside Bedroom
	Inside Kitchen	YES	YES	Inside Kitchen


BCH DESIGN GUIDELINES - 1 BEDROOM

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	49 m ²	YES	53 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1280 mm
5.3.2.1	Living Room seating capacity	4 seats	YES	4/5 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	920 mm
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	1015 mm
5.3.3.1	Dining Room seating capacity	4 seats	YES	4 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	1.5 m ² in Parkade TBD
5.4.2	Bedroom type	1 Type B	YES	10.81 m ²
	Type B: Min Area	9.30 m ²	YES	2800 mm
	Type B: Min Dimension	2800 mm	YES	1805 mm
	Type B: Closet width	1500 mm	YES	1805 mm
5.5.1.1	Provide 2.3 sm of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	Bedroom Closet
6.1.3	Counter Frontage Recornd.	2440 mm	YES	3020 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	915 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	800 mm
6.2.3.1	3 Piece Bathroom	1	YES	815 x 1525 mm tub
	Shower (914 x 1220mm)	NO	NO	1
	Water Closet	YES	YES	1
	Lav Basin with Vanity	YES	YES	1

NOTE:
UNIT AREA CALCULATED FROM THE CENTRE LINE OF DEMISING WALLS, CENTRE LINE OF CORRIDOR WALLS AND OUTSIDE FACE OF SHEATHING ON EXTERIOR WALLS.

BCH DESIGN GUIDELINES - 1 BEDROOM

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	49 m ²	YES	50 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1370 mm
5.3.2.1	Living Room seating capacity	4 seats	YES	4/5 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	920 mm
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	1015 mm
5.3.3.1	Dining Room seating capacity	4 seats	YES	4 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	1.5 m ² in Parkade TBD
5.4.2	Bedroom type	1 Type B	YES	9.30m ²
	Type B: Min Area	9.30 m ²	YES	3000 mm
	Type B: Min Dimension	2800 mm	YES	1310 mm - 868 mm
	Type B: Closet width	1500 mm	YES	Bedroom Closet
5.5.1.1	Provide 2.3 sm of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	3020 mm
6.1.3	Counter Frontage Recornd.	2440 mm	YES	915 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	800 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	800 mm
6.2.3.1	3 Piece Bathroom	1	NO	815 x 1525 mm tub
	Shower (914 x 1220mm)	NO	NO	1
	Water Closet	YES	YES	1
	Lav Basin with Vanity	YES	YES	1




SUITE TYPE A2 (STUDIO 02) 36 m² (387.9 sf)

1:50


BCH DESIGN GUIDELINES - STUDIO

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	33 m ²	YES	36 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1170 mm
5.3.2.1	Living Room seating capacity	2 seats	YES	2 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	920 mm
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	1015 mm
5.3.3.1	Dining Room seating capacity	2 seats	YES	2 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	1.5 m ² in Parkade TBD
5.4.2	Bedroom type	N/A	N/A	N/A
5.5.1.1	Provide 2.3 sm of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	2875 mm
6.1.3	Counter Frontage Recornd.	1860 mm	YES	915 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	800 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	800 mm
6.2.3.1	3 Piece Bathroom	1	NO	815 x 1525 Bathub
	Shower (914 x 1220mm)	NO	NO	1
	Water Closet	YES	YES	1
	Lav Basin with Vanity	YES	YES	1



SUITE TYPE B1 50 m² (533 sf) & 52.8 m² (568 sf) & 55.5 m² (608 sf)

1:50




SUITE TYPE A1 (STUDIO 01) 35.5 m² (382.3 sf)

1:50

BCH DESIGN GUIDELINES - STUDIO


SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/COMMENTS
5.2	Unit Area	33 m ²	YES	35.5 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1370 mm
5.3.2.1	Living Room seating capacity	2 seats	YES	3 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	920 mm
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	1015 mm
5.3.3.1	Dining Room seating capacity	2 seats	YES	2 seats
5.4.1.3	Door open full	110 degrees	NO	110 degrees
5.4.1.4	Access bed - foot and 2 sides	YES	YES	1.5 m ² in Parkade TBD
5.4.2	Bedroom type	N/A	N/A	N/A
5.5.1.1	Provide 2.3 sm of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	2710 mm
6.1.3	Counter Frontage Recornd.	1860 mm	YES	915 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	800 mm
6.2.2.3	Towel Bar Min. Width	800 mm	YES	800 mm
6.2.3.1	3 Piece Bathroom	1	NO	815 x 1525 Bathub
	Shower (914 x 1220mm)	NO	NO	1
	Water Closet	YES	YES	1
	Lav Basin with Vanity	YES	YES	1





SUITE TYPE E1 @ L1 128.9 m² (1387sf)

1 : 50



SUITE TYPE E1 @ L2

1 : 50


BCH DESIGN GUIDELINES - 4 BEDROOM

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/ COMMENTS
5.2	Unit Area	112 m ²	YES	125.8 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1500 mm
5.3.2.1	Living Room seating capacity	7 seats	YES	7 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	-
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	-
5.3.3.1	Dining Room seating capacity	8 seats	YES	8 seats
5.4.1.3	Door open full	110 degrees	NO	-
5.4.1.4	Access bed - foot and 2 sides	YES	YES	-
5.5.1.1	Provide 2.3 m of storage	YES	YES	2.3 m ²
5.5.1	Provide Linen Closet	YES	YES	-
6.1.3	Counter Frontage Recornd.	2890 mm	YES	4665 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	915 mm
6.2.2.3	Towel Bar Min. Width	900 mm	YES	-
6.2.3.1	3 Piece Bathroom	1	YES	YES
	Shower (914x1220mm) or ST tub	YES	YES	815 x 1525 mm tub
	Water Closet	1	YES	1
6.2.5	Lav Basin with Vanity	1	YES	1
	Powder Room	1	YES	1
	Water Closet	1	YES	1
	Lav Basin with Vanity	1	YES	1

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/ COMMENTS
5.4.2	Bedroom type 1 A / 1 B / 2 C	YES	YES	-
	Type A: Min Area	11.15 m ²	YES	13.08 m ²
	Type A: Min Dimension	2800 mm	YES	2810 mm
	Type A: Closet width	1500 mm	YES	2050 mm
	Type B: Min Area	9.30 m ²	YES	9.52 m ²
	Type B: Min Dimension	2800 mm	YES	2885 mm
	Type B: Closet width	1500 mm	YES	1580 mm
	Type C1: Min Area	8.50 m ²	YES	8.58 m ²
	Type C1: Min Dimension	2600 mm	YES	2600 mm
	Type C1: Closet width	915 mm	YES	1530 mm
	Type C2: Min Area	8.50 m ²	YES	8.58 m ²
	Type C2: Min Dimension	2600 mm	YES	2600 mm
	Type C2: Closet width	915 mm	YES	1380 mm

NOTE:

UNIT AREA CALCULATED FROM THE CENTRE LINE OF DEMISING WALLS, CENTRE LINE OF CORRIDOR WALLS AND OUTSIDE FACE OF SHEATHING ON EXTERIOR WALLS. TOWNHOUSE INTERIOR STAIR AREAS ARE ONLY CALCULATED AT GROUND LEVEL.



SUITE TYPE D


90.8 m² (977.6 sf)

1 : 50

BCH DESIGN GUIDELINES - 3 BEDROOM


SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/ COMMENTS
5.2	Unit Area	88 m ²	YES	88 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	1000 mm
5.3.2.1	Living Room seating capacity	8 seats	YES	8 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	-
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	-
5.3.3.1	Dining Room seating capacity	6 seats	YES	8 seats
5.4.1.3	Door open full	110 degrees	NO	-
5.4.1.4	Access bed - foot and 2 sides	YES	YES	-
5.5.1.1	Provide 2.3 m of storage	YES	NO	1.5 m ² in Parkade TBD
5.5.1	Provide Linen Closet	YES	YES	-
6.1.3	Counter Frontage Recornd.	2890 mm	YES	3475 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	915 mm
6.2.2.3	Towel Bar Min. Width	900 mm	YES	-
6.2.3.1	3 Piece Bathroom	1	YES	YES
	Shower (914x1220mm) or ST tub	YES	YES	815 x 1525 mm tub
	Water Closet	1	YES	1
6.2.5	Lav Basin with Vanity	1	YES	1
	Powder Room	1	YES	1
	Water Closet	1	YES	1
	Lav Basin with Vanity	1	YES	1

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/ COMMENTS
5.4.2	Bedroom type 1 A / 1 B / 1 C	YES	YES	-
	Type A: Min Area	11.15 m ²	YES	11.13 m ²
	Type A: Min Dimension	2800 mm	YES	3135 mm
	Type A: Closet width	1500 mm	YES	2185 mm
	Type B: Min Area	9.30 m ²	YES	9.72 m ²
	Type B: Min Dimension	2800 mm	YES	3100 mm
	Type B: Closet width	1500 mm	YES	1880 mm
	Type C: Min Area	8.50 m ²	YES	8.53 m ²
	Type C: Min Dimension	2600 mm	YES	2600 mm
	Type C: Closet width	915 mm	YES	1570 mm



SUITE TYPE E2 @ L1 128.9 m² (1387sf)

1 : 50



SUITE TYPE E2 @ L2

1 : 50

BCH DESIGN GUIDELINES - 4 BEDROOM

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/ COMMENTS
5.2	Unit Area	112 m ²	YES	122.6 m ²
5.3.1.1	Suite Entry-Closet Min. Width	915 mm	YES	915 mm
5.3.2.1	Living Room seating capacity	7 seats	YES	7 seats
5.3.2.2	Circulation spaces Min. Width	920 mm	YES	-
5.3.2.3	Interior Corridor Recornd. Width	1015 mm	YES	-
5.3.3.1	Dining Room seating capacity	8 seats	YES	8 seats
5.4.1.3	Door open full	110 degrees	NO	-
5.4.1.4	Access bed - foot and 2 sides	YES	YES	-
5.5.1.1	Provide 2.3 m of storage	YES	YES	2.3 m ²
5.5.1	Provide Linen Closet	YES	YES	-
6.1.3	Counter Frontage Recornd.	2890 mm	YES	4665 mm
6.2.2.2	Lav. Countertop Min. Width	900 mm	YES	915 mm
6.2.2.3	Towel Bar Min. Width	900 mm	YES	-
6.2.3.1	3 Piece Bathroom	1	YES	YES
	Shower (914x1220mm) or ST tub	YES	YES	815 x 1525 mm tub
	Water Closet	1	YES	1
6.2.5	Lav Basin with Vanity	1	YES	1
	Powder Room	1	YES	1
	Water Closet	1	YES	1
	Lav Basin with Vanity	1	YES	1

SECTION	DESCRIPTION	BCH	PROVIDED	VALUE/ COMMENTS
5.4.2	Bedroom type 1 A / 1 B / 2 C	YES	YES	-
	Type A: Min Area	11.15 m ²	YES	11.26 m ²
	Type A: Min Dimension	2800 mm	YES	3250 mm
	Type A: Closet width	1500 mm	YES	1500 mm
	Type B: Min Area	9.30 m ²	YES	10.57 m ²
	Type B: Min Dimension	2800 mm	YES	3000 mm
	Type B: Closet width	1500 mm	YES	1500 mm
	Type C1: Min Area	8.50 m ²	YES	9.70 m ²
	Type C1: Min Dimension	2600 mm	YES	2600 mm
	Type C1: Closet width	915 mm	YES	1400 mm
	Type C2: Min Area	8.50 m ²	YES	8.58 m ²
	Type C2: Min Dimension	2600 mm	YES	2600 mm
	Type C2: Closet width	915 mm	YES	1380 mm














PRELIMINARY - NOT FOR CONSTRUCTION

PRELIMINARY - NOT FOR CONSTRUCTION

AREA SCHEDULE - GROSS BUILDING		
Name	Area (sqm)	AREA (sqft)
LEVEL 1	1642.8 m ²	17683 ft ²
LEVEL 2	1690.7 m ²	18199 ft ²
LEVEL 3	1690.7 m ²	18199 ft ²
LEVEL 4	1690.7 m ²	18199 ft ²
LEVEL 5	1690.7 m ²	18199 ft ²
LEVEL 6	1599.3 m ²	17215 ft ²
Grand total	10005 m ²	107693 ft ²

TOTAL AREA:
8220 m²



NOTE:
FAR IS CALCULATED FROM THE CENTRE LINE OF PARTY WALLS, CORRIDOR WALLS
AND THE INSIDE FACE OF EXTERIOR WALL AND INCLUDE ALL INTERIOR STORAGE,
AND EXCLUDE STAIRS, ELEVATOR SHAFT, CORRIDORS, LAUNDRY, AMENITY
ROOMS AND WATER CLOSETS.
GROSS AREA IS CALCULATED FROM FACE OF EXTERIOR SHEATHING.




AERIAL VIEW

VIEW FROM FLEMING STREET


PRELIMINARY - NOT FOR CONSTRUCTION




PRELIMINARY - NOT FOR CONSTRUCTION




3 EAST WEST SECTION 03
D15 1:150



SECTION KEY PLAN



2 EAST WEST SECTION 02
D15 1:150



1 EAST WEST SECTION 01
D15 1:150




LOW HAMMOND ROWE ARCHITECTS




ESQUIMALT RENTAL HOUSING
874 FLEMING STREET, ESQUIMALT, BC

EAST WEST SECTIONS **D15**
scale indicated date 2020.02.11







SECTION KEY PLAN

RECEIVED
FEB 11 2020
CORP. OF TOWNSHIP
OF ESQUIMALT
DEVELOPMENT SERVICES



PRELIMINARY - NOT FOR CONSTRUCTION




RECEIVED
FEB 11 2020
CORP. OF TOWNSHIP
OF ESQUIMALT
DEVELOPMENT SERVICES


PRELIMINARY - NOT FOR CONSTRUCTION




2 NORTH SOUTH SECTION 04
D18
D18 1:150



SECTION KEY PLAN




3 NORTH SOUTH SECTION 07
D15
D18 1:100



1 NORTH SOUTH SECTION 03
D18
D18 1:150




PRELIMINARY - NOT FOR CONSTRUCTION



2 D19 NORTH SOUTH SECTION 06
D19 1:150

SECTION KEY PLAN



1 D19 NORTH SOUTH SECTION 05
D19 1:150



PRELIMINARY - NOT FOR CONSTRUCTION

The intended print size is 11" by 17".


For full tree details refer to Construction Impact Assessment & Tree Preservation Plan provided by Talbot Mackenzie & Associates dated June 26, 2019

Lot Area = 3909m²

Drawing	2826 BCLS Site02
File	12,826 - 23

POWELL & ASSOCIATES
 B C Land Surveyors
 250-2950 Douglas Street
 Victoria, BC V8T 4N4
 phone (250) 382-8855

**CORP. OF TOWNSHIP
OF ESQUIMALT
DEVELOPMENT SERVICES**



M76301 - Undersurface Rights
106260G - Undersurface Rights
A64775 - Restrictive Covenant

Scott Pearse
1BUGAM

Digitally signed by Scott Pearse 1BUGAM
DN: cn=C=A, cn=Scott Pearse 1BUGAM, o=BC
Land Surveyor, ou=Verify ID at
www.juricert.com/LKUP.cfm?tid=1BUGAM
Date: 2020.02.06 13:05:56 -08'00'

Scott T. Pearse, B.C.L.S. 

This document is not valid unless digitally signed and sealed.



Image 1. Katsura Tree

Recommended Nursery Stock

Trees				
ID	Quantity	Botanical Name	Common Name	Size
CeJa	3	Cercidiphyllum japonicum	Katsura Tree	6 cm cal.
MaGa	7	Magnolia Galaxy	Galaxy Magnolia	6 cm cal.
PinI	2	Pinus nigra	Black pine	6 cm cal.
PsMe	7	Pseudotsuga menziesii	Douglas Fir	3 m ht.
Large Shrubs				
ID	Quantity	Botanical Name	Common Name	Size
ChTe	11	Choisya ternata	Mexican Orange Blossom	# 5 pot
CoCo	6	Colinus coggygia	Smoke Bush	# 7 pot
Medium Shrubs				
ID	Quantity	Botanical Name	Common Name	Size
CoSt	20	Cornus stolonifera	Redtwig Dogwood	# 5 pot
RiSa	33	Ribes sanguineum	Red Flowering Currant	# 5 pot
RoNu	31	Rosa nutkana	Nootka Rose	# 2 pot
RuSp	29	Rubus spectabilis	Salmonberry	# 2 pot
SaRu	121	Sarcococca ruscifolia	Sweet Box	# 1 pot
Small Shrubs				
ID	Quantity	Botanical Name	Common Name	Size
GaSh	264	Gaultheria shallon	Salal	# 1 pot
SkJa	31	Skimmia japonica	Skimmia	# 1 pot
SpDo	73	Spirea douglasii	Hardhack	# 1 pot
Perennials, Annuals and Ferns				
ID	Quantity	Botanical Name	Common Name	Size
AcMi	85	Achillea millefolium	Common White Yarrow	# 1 pot
AsYo	68	Astilbe younique white	Dwarf Astilbe	# 1 pot
EcPu	241	Echinacea purpurea	Purple Coneflower	SP4
MiSi	69	Miscanthus sinensis	Japanese Silver Grass	# 5 pot
PeAl	71	Pennisetum alopecuroides	Fountain Grass	# 1 pot
PoMu	113	Polystichum munitum	Sword Fern	SP4
RuFu	201	Rudbeckia fulgida 'Goldsturm'	Goldsturm Black Eyed Susan	SP4

- Notes:
1. All work to be completed to current BCSLA Landscape Standards
 2. All soft landscape to be irrigated with an automatic irrigation system




Image 2. Evergreen screen with Douglas fir




Image 3. Galaxy Magnolia Tree




Image 4. Vine Maple Tree

Existing mature Arbutus tree to be retained and protected

Planted areas with Sweetbox hedge, Ornamental grasses, Red Flowering Currant, and Salal surround surface parking area

Katsura tree in front gardens (Typical.)



Copyright Reserved. These drawings are at all times the property of the Landscape Architect. Reproduction in whole or in part without written consent of the Landscape Architect is prohibited.



C.	Feb 10, '20	Rezoning Submission Revisions
B.	Oct 22, '19	Revised Rezoning Submission
A.	Aug 19, '19	Rezoning Submission

REVISIONS



#3-864 Queens Ave. Victoria B.C. V8T 1M5
Phone: (250) 598-0105 Fax: (250) 412-0696

PROJECT

874 Fleming St.
Esquimalt, B.C.

TITLE

Landscape Concept
Plan

SCALE As shown
DRAWN O.L.
CHECKED B.W.

PROJECT No 1907

DATE Oct 22, 2019
SHEET 1 of 1